Project Summary / Program Statement:

CONEY ISLAND, one of five **BOLD BOOTHS**, is a 60 square-foot pavilion that replaces a derelict one used to operate the parking lot for the Westin Hotel and the historic Southern Theater housed within. The Theater departed from the classical opera house by incorporating features considered unique for its day. Most notable was the design of the audience chamber ceiling and the proscenium. The geometry of this volume is generated from a series of conic sections that create a space still considered to be nearly perfect acoustically. Adjacent to the theater, **CONEY ISLAND** re-engineers this series of conic sections to address a new agenda.

The project's geometries could not be realized through conventional means of construction or materials. Flame resistant EPS foam was selected for its ability to be digitally tooled and its high insulation value. The seamless EPS is completed through an assembly of performance coatings. This composite material works equally well as both interior and exterior finish.

Within a compact and sculptural space, tools of the parking lot valet trade are accounted for and absorbed by the space's shell. Tabs create flat areas on the curving interior surface for built-in storage, shelf, time clock, air conditioning supply and return, and thermostat. Additional elements, such as key organization, stool, and desk are made from laminated, clear-coated plywood. The warmth of the material, whose layers and grain have been exposed through cutting and milling, provide a counterpoint to the seamlessness of the white conics.

Finally, establishing engagement between parking lot attendants and visitors, the interior volume breaks through a staid box forming apertures. From the inside, like the periscope of a submarine, attendants get commanding views of their territory. From the outside, visitors get framed views that reveal the surprising complexity of the interior space and it's embedded programmatic elements.

B39.01

Submission Type: Built Award

Project Location: Columbus, OH

Project Completion Date: **05/2015**


Project Type: New Construction

Use Type: Commercial




BOLD BOOTHS is a collection of site-specific parking attendant pavilions designed to reframe the seemingly mute, desolate, and ubiquitous parking lots upon which they sit. Micro-buildings once valued merely for their ability to watch over vehicles in exchange for dollar bills and credit card swipes resist expectations to become surprising cultural exchange points in the city.


The first site of five future booths (next to the historic Great Southern Theater), showing the pre-existing attendant booth.




BOLD BOOTH Sites




The Great Southern Theater and the Westin Great Southern Hotel sit within an attractive brick box that fits nicely within the urban fabric but veil interior secrets: a fantastic lobby, a long-lost roof garden, and a unique proscenium theater formed from conic sections. It is this hidden geometry of the theater that CONEY ISLAND re-engineers.






Three cones were carefully oriented within the parking lot to obtain views of Main Street, collect rainwater, and create inhabitable space. As the cones interact, a theatrical work space is produced.

.





The resultant form is thickened according to insulation needs and embedded functions. The exterior scoop sheds water from the flat roof area The foam thickens to match via a milled scupper. the framed enclosure and Blocking pockets to attach has a tooled slot into which sheathing fits. to the conventionally framed Blocking embedded in EPS Tabs flatten the curving foam allows for installation geometry to allow for the of portal window. installation of equipment. Sleeve for a steel bracket that resists uplift. Pocket for a built-in storage unit.

B39.04

Through controlled inflation of the form's thickness, we smoothly calibrated from five inches to get a R-value of 20 (where R-17 is code for "wall assemblies") to R-38 (code for "roof assemblies") and well beyond. Important for the pavilion's attendants, comfortable temperatures are retained in a space where day-to-day operations demand that the door is constantly opened and closed.

Embedded in the foam form are the means of connecting conventional components (framing, windows, and sheathing), as the diagram at left illustrates.



view from the parking lot entrance looking towards Main Street




view looking west towards rain garden





view in (through the stainless steel yoke) and view out to the parking lot.










view into the work area and view of integrated desk and stool

MAIN STREET













party in the parking lot